

Notes to Part 7

Fire Emergency Systems in High Buildings

A-7.2.1.1.(1) It is not intended that all equipment be tested on each test occasion. A representative number of devices may be tested on each occasion provided all equipment is tested within the time period agreed to in the fire safety plan.

A-7.3.1.1.(1) The testing required in Section 7.3. is not intended to be a complete assessment of the design of the smoke control system, but only a test of the individual pieces of equipment specified.